



दूरध्वनी :022- 25331590

फॅक्स: 022- 25364779

ठाणे महानगरपालिका

महानगरपालिका भवन, डॉ. अल्मेडा रोड, चंदनवाडी, पाचपाखाडी, ठाणे-४००६०२

THE MUNICIPAL CORPORATION OF THE CITY OF THANE

संदर्भ क्र/ ठा.म.पा/कार्यअभि/वि/११०२
Ref./T.M.C./EE/ELE/

दिनांक ०४ / ०९ / २०१९
Date / / 2019

नोटीस

विषय :- ठाणे महानगरपालिकेच्या बेसमेंट मधील विद्युत विभागात Fan Coil Unit व त्या अनुषंगिक आवश्यक कामे करणे.

(अंदाजखर्च - रु. १,७७,५६१/-)

महोदय,

वरील विषयांकित कामाकरीता ठाणे महानगरपालिका विद्युत विभाग, संबंधित क्षेत्रातील मान्यता प्राप्त ठेकेदाराकडून टक्केवारी दराची मोहोरबंद दरपत्रके मागवित आहेत. सदर कामाची दरपत्रके दि.०४/०९/२०१९ ते दि. १३/०९/२०१९ या कालावधीत सकाळी ११.०० ते सायंकाळी ४.०० वाजेपर्यंत नागरी सुविधा केंद्र ठाणे महानगरपालिका ठाणे येथे स्विकारण्यात येतील. मुदतीनंतर आलेल्या दरपत्रकांचा विचार केला जाणार नाही. याची कृपया नोंद घ्यावी.

अटी:

- १) उद्योग उर्जा कामगार विभाग, महाराष्ट्र शासना कडून देण्यात आलेला विद्युत ठेकेदारांचा अनुज्ञापत्राचा दाखला सादर करणे बंधनकारक राहिल.
- २) शासकीय, निम शासकीय व स्थानिक स्वराज्य संस्थाकडे समकक्ष काम पूर्ण केल्याचा दाखला सादर करणे बंधनकारक राहिल.
- ३) GST नोंदणी दाखला सादर करणे बंधनकारक राहिल.
- ४) भविष्य निर्वाह निधी नोंदणी दाखला सादर करणे बंधनकारक राहिल.

सोबत: अंदाजखर्च

सही/-
विनोद गुप्ता
कार्यकारी अभियंता (वि)
विद्युत विभाग, ठामपा.

THANE MUNICIPAL CORPORATION, THANE

ABSTRACT

SUB: Providing & Erecting FAN COIL UNIT at Basement In Main Admin Bldg .

SR.NO	DESCRIPTION	C.S.R.NO	QTY	UNIT	RATE	AMOUNT
1	S & E of 1.5 TR Fan Coil Unit	MR	2	EACH	26782.00	53564.00
	TECHNICAL DETAILS. Dimension of Unit H.345.W.1340. D.605. CFM.800 Motor HP 1/12, RPM 900 No. Speed .3. Coil Details .No of Rows .3. Surface Area 2.53 SQFT. Tube Dia. 1/2" Fin Spacing 12 FPI .Drain Pan. 20 GI with 13mm thick Nitrile Insulation . Blower Details 8" x 7" .					
2	S & E of Ball Valve for Drain and Vent System of having size if 1.5" dia for drainage & air venting out at chilled water system	MR	4	EACH	1688.00	6752.00
3	Supplying , Laying/fixing , testing& commissioning of appropriate normal refrigerant copper pipe of 41.3 mm dia (OD) for liquid line /Suctio line supply and return piping of suitable guage (hard drawn copper pipe for liquid main line and main for refrigerant) along with necessary supports , hanger, clamps, vibration isolators and fitting such as bends tees , valves, guages strainers with insulation of 19 mm thick elastomeric nitrile rubber along with application of multi coating suitable for use with VRV/VRF piping for protection against mechanical damages funal growth, flame spread, water permeance and ultra violet radiations complete with OEM Standards of VRV/VRF air-condition system.	3.11.89	28	MTR	2398.00	67144.00
4	Two Way Solenoid Valve	MR	2	EACH	11460.00	22920.00
5	Providing of extra drain piping	MR	15	MTR	75.00	1125.00
6	Supply & erecting cast iron double flange butterfly valve of size 50 mm dia. complete as per specification no. FF-VL/BFV	13.6.13	2	EACH	2143.00	4286
7	Supplying and erecting G.I. pipe above ground of 'C' class ERW of size 50 mm dia with necessary fitting complete as per specification no.FF-PP	13.5.3	10	MTR	677.00	6770
8	Draining of water from complete system fixing of valve & piping for the connection of fan coil unit. Refilling of water of water remvin of airlock and putting the system in working condition.	MR	1	JOB	15000.00	15000
			TOTAL	RS.		177561.00

I / We agree to execute the above work at % above/ below/ at par the above estimate cost

Contractor